

# WATER TEST PROCEDURE

STEP 1:

BLANK OFF ALL TANK FITTINGS.

STEP 2:

FILL TANK WITH CLEAN WATER TO TOP OF STRAIGHT SIDE. NO CHEMICALS ARE TO BE USED FOR TEST.

STEP 3:

ALLOW WATER TO SET FOR MINIMUM OF 6 HOURS.

STEP 4 :

OBSERVE TANK FOR LEAKS.

STEP 5:

DRAIN TANK

WATER TEST COMPLETE.